


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Ellis County. Sec. 21 Twp. 11S Rge. 16W ~~XX~~ ~~XX~~  
Location as "NE/CNW/SW" or footage from lines SE SW SE  
Lease Owner El Dorado Refining Co.  
Lease Name McGuire Well No. 1  
Office Address 306 Koch Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8-26-53 19  
Application for plugging filed 10-19-53 19  
Application for plugging approved 19  
Plugging commenced 8-25-53 19  
Plugging completed 8-26-53 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3460 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy drilling mud, set plug and forced plug out with 80 sacks of Portland Cement under 400# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 22 1953

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company  
Address 1005 Central Bldg., Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss. Prime Drilling Co. Contractor  
Prime Drilling Co. of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 20 day of October, 19 53

[Signature]  
Notary Public.

My commission expires Oct. 29, 1955



ROTARY DRILLING LOG

OPERATOR: El Dorado Refining Co.  
 McGuire #1  
 SE SW SE Sec. 21-11S-16W  
 Ellis County, Kansas

CONTRACTOR: Prime Drilling Co.  
 COMM: 8-13-53  
 COMP: 8-26-53

FORMATION

REMARKS

Surface clay & Rock	60'
Shale	417'
Sand & Iron	535'
Sand	750'
Red Bed	775'
Red Bed & Pyrite	991'
Anhydrite	1035'
Shale & Red Bed	1240'
Shale & Shells	1773'
Shale	1920'
Shale & Lime	2920'
Lime	3015'
Shale & Lime	3035'
Lime	3349'
Conglomerate	3396'
Arbuckle	3460'
Total Depth	3460'

8 5/8" Csg. set @ 997'  
 Cemented W/500 sks. cement  
 with 3 sks. c.c.

We certify that the above log is true  
 and correct to the best of our  
 knowledge and belief.

PRIME DRILLING COMPANY

By *L. J. [Signature]*

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 22 1953  
 CONSERVATION DIVISION  
 Wichita, Kansas

21-11-16W  
 125-21