


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-051-00659-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Ellis County, Sec. 21 Twp. 11 Rge. 16 (E) (W)
Location as "NE/CNW¹/₄SW¹/₄" or footage from lines SE SE NW
Lease Owner Great Lakes Carbon Corp. & Anschutz Drilling Co., Inc.
Lease Name McGuire Well No. 1
Office Address Petroleum Bldg. (former) 709 Union Nat'l Bk Bldg. both in Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-13-1951
Application for plugging filed 6-13 1951
Application for plugging approved 6-13 1951
Plugging commenced 6-13 1951
Plugging completed 6-13 1951
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3393 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	957'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 200' with 20 sacks cement.
Top plug set at 55' with 15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1951
6-23-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Great Lakes Carbon Corp.
Address Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
M. W. Smith (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *M. W. Smith*

709 Union Nat'l Bk. Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of June, 1951
Laura Stecker
Notary Public.

My commission expires January 21, 1951

28-5091-s 8-50-10M



PLUGGING
FILE SEC 21 T 11 R 16
BOOK PAGE 86 LINE 20

15-051-00659-0000

MCGUIRE NO. 1 WELL

Location: SE/4 SE/4 NW/4 Sec. 21-11S-16W Spudded: 5-31-51
 Ellis County, Kansas Completed: 6-13-51
 Operator: Anschutz Drilling Co., Inc. Elevation: 1777' RB
 Contractor: Fred Drilling Co.
 Surface Casing: 30 jts. 8-5/8" set @ 955.16'
 w/525 sacks cement and 2 sacks
 Cal. Chloride
 Oil String: None - D&A

T O P S R B

Anhydrite	945 (+ 832)
Heebner	2957 (-1180)
Toronto	2978 (-1201)
Lansing-Kansas City	3006 (-1229)
Chert Conglomerate	3315 (-1538)
Simpson	3334 (-1557)
Arbuckle	3356 (-1579)
Total Depth	3393 (-1616)

L O G

(Figures indicate bottom of formation)

Sand shale	0 to 312
Shale and sand	365
Sand	460
Shale	745
Sand	905
Shale	945
Anhydrite	953
Anhydrite	980
Shale sand and shells	1215
Shale and sand	1570
Shale - shells	1745
Shale lime	1900
Shale and lime	1990
Lime - shale	2080
Lime and shale	2290
Shale - lime	2415
Shale	2550
Shale and lime	2645
Shale - lime	2745
Lime and shale	2865
Lime - shale	2900
Lime	2940
Lime and shale	3148
Lime	3198
Lime and shale	3315
Chert Conglomerate	3332
Conglomerate and shale	3364
Total Depth	3393'

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 23 1951
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

FRED DRILLING CO.

By Robert F. Walters

Subscribed and sworn to before me this 15th day of June 1951.

Mary L. Lawrence
 Notary Public

PLUGGING
 FILE SEC 21-11-16W
 BOOK PAGE 88 LINE 20

My commission expires: Feb. 28, 1955