

LEASE NAME Chrysler "B"

WELL NUMBER 1

4,290 Ft. from S Section Line

2,970 Ft. from E Section Line

SEC. 21 TWP. 11 RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed 11-29-96

Plugging Commenced 11-29-96

Plugging Completed 11-30-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR ESP Development, Inc.

ADDRESS 17746 177th Blvd., Paradise, KS. 67658

PHONE#(913) 998-4413 OPERATORS LICENSE NO. 6,194

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-29-96 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	223'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each section. Push bridge plug to 975', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 500', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 10 sax cement down mouse hole and 15 sax cement down rat hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5,184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ESP Development, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Contractor) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.


(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS.

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 96

Ruth Phillips  
Notary Public

My Commission Expires: \_\_\_\_\_





# Shields


## WELL LOG

15-051-24945-0000

Russell, Kansas

Operator: ESP Development, Inc.  
 Well: Chrisler "B" #1  
 Commenced: November 22, 1996  
 Completed: November 30, 1996  
 Contractor: Shields Drilling Co.

Well Description: SE NE NW  
 Sec. 21-11S-16W  
 Ellis County, Kansas



### CASING RECORD

Size	Run	Pulled
8 5/8"	223'	Cmtd. w/150 sax

Elevation:  
 Treatment: 1,774' KB  
 Production: D & A  
 Tops:

..... Figures Indicate Bottom of Formations .....

Sand, shale & rock	30'
Sand & shale	226'
Shale	937'
Anhydrite	974'
Shale	2,979'
Lime	3,360' RTD

12091150  
 KANSAS CORP CORM  
 1996 DEC 12 A 12:28