


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
900 Bitting Building
Wichita, Kansas

Stafford

County, Sec. 2 Twp. 21 Rge. 13 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW
Lease Owner National Cooperative Refinery Association
Lease Name Address "A" Well No. 1
Office Address 820 Union National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 5-12 19 49
Application for plugging filed 6-25 19 52
Application for plugging approved 6-27 19 52
Plugging commenced 7-23 19 52
Plugging completed 8-23 9-23 19 52
Reason for abandonment of well or producing formation Production Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 4-27 19 52
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Kansas City Depth to top 3371 Bottom 3375 Total Depth of Well 3375 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	197'	Cemented
				5 1/2"	3513'	2861.84'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole from 3375' to 3315'; Run 5 Sacks cement. Mudded hole to 200', set 20' Rock Bridge, dumped 20 sxs. cement. Mudded hole to 35', dumped 10 sxs. cement on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. Jean La Coss (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Jean La Coss
820 Union National Bank Building (Address)

SUBSCRIBED AND SWORN to before me this 28 day of July, 1952

My commission expires February 20, 1953

23-8390-s 6-51-20M

PLUGGING
FILE SEC 2 T 21 R 13
BOOK PAGE 36 LINE 17

I. A. Lange Notary Public
RCW
07-29-52
CONSERVATION DIVISION
Wichita, Kansas

15785 00767-0000
C
O
P
Y

C
O
P
Y

Owner: Armer Drilling Company, Inc.
Contractor: Armer Drilling Company, Inc.
Drilling Commenced: 4/27/49
Drilling Completed: 5/12/49
Elevation: 1870'
Rotary Rig #2

Farm: Address #1
Location: NE NE SW 1/4 Sec. 2-21-13W
Stafford County
Casing record: 8 5/8" @ 197' cem
w/200 sacks cement.
5 1/2" @ 3513' cemented
w/125 sacks cement

(figures below indicate bottoms)

Sand	120	
Shale & shells	192	
Iron & shale	197	
Surface clay & sand	250	
Red bed	540	
Red bed & shells	703	
Anhydrite	733	
Shale & shells	1575	
Lime	1580	
Shale & lime	1960	
Lime	1975	
Shale	2015	
Shale & shells	2245	
Shale & lime	2370	
shale & shells	2500	
Shale	2655	
Shale & lime	3268	
Lime	3485	
Shale & lime	3509	
Shale	3512	
Dolomite - Total Depth	3515	Rotary

(all rotary bushing measurements)
TOPS:

Lansing-KC	3243	
Cherty conglomerate	3493	
Simpson shale	3496	
Simpson dolomite	3501	
Simpson Shale	3504	
Arbuckle dolomite	3512	
Cable	3528	TD

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

Armer Drilling Company, Inc.

By L. C. Sponenberg /s/

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, in and for said County and State this 16th day of May, 1949.

Hazel Walton /s/
Notary Public

My commission expires Sept. 17, 1951.

RECEIVED
THE COMMISSIONER OF CONSERVATION
JUL 27 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 2 T 2 R 13
BOOK PAGE 26 LINE 7