

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-22437-0000

LEASE NAME BOWLBY 'A'

WELL NUMBER NO. 1

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

4950 Ft. from (S)N Line of Section (circle one)

4290 Ft. from (E)W Line of Section (circle one)

LEASE OPERATOR E.S.P. DEVELOPMENT CO. INC.

SPOT LOCATION C - NE - NW - NW

ADDRESS RR #1 BOX 18

SEC. 26 TWP. 11S. RGE 16W (E) or (W)

CITY, STATE, ZIP PARADISE, KANSAS 67658

COUNTY ELLIS

PHONE#(913) 998-4413 OPERATORS LICENSE NO. 6194

Date Well Completed 6/1981

Charater of Well Producing 3 B.O.P.D.

Date Plugging Commenced July 20, 1995

(Oil), Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Completed July 20, 1995

Casing failure created negative R.O.I.

The plugging proposal was approved on July 19, 1995 (date)

by HERB DIENES (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation(s) Topeka, & Lsg. K.C. Depth to Top 2686' Bottom 3162' T.D. 3380'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Dakota	Sand Wtr. Snd.	250'	750'	8 5/8"	170'	None
Topeka	IM.	2656'	2900'	4 1/2"	3378'	None.
L.K.C.	Im.	2950'	3184'			
Marmaton	Sndy Im.	3200'	3320'			

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Perforate 4 1/2" casing @ 1550', 900' & 700', Csg. leak @ 520'

Cast Iron Bridge Plug @ 2610', Run tubing to 2570', spot 10 Bls. Gel, followed by 8 Sx. cement.

Pull tubing to 1600', Circulate cement to surface(60/40 Poz 10% Gel.) Pulled tubing out of

hole, squeeze down casing with 125 Sx. Max. pressure 300#. Total cement 225 Sx in hole.

Pressure annulus between 8 5/8" and 4 1/2" casing. Unable to pump in @ 1500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING CO.

License No. N.A.

Address RUSSELL, KANSAS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: E.S.P. Development Co.

STATE OF KANSAS COUNTY OF ELLIS, ss.

CHARLES D. FARR (Cons. Eng.) (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles D. Farr

(Address) 209 W. 33 St., Hays, Kans. 67601

SUBSCRIBED AND SWORN TO before me this 21st day of July, 1995

Karie L. Younger
Notary Public

My Commission Expires: 7-10-96

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1995

CONF. FOWA/HALES/STON
WICHITA, KANSAS

