


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-01215-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 26 Twp. 11S Rge. 16 (X) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Davis Bros.-Transit Corporation
Lease Name Shaw "B" Well No. 1
Office Address 1516 Liberty Bank Building-Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed November 26, 19 58
Application for plugging filed November 26, 19 58
Application for plugging approved November 26, 19 58
Plugging commenced November 26, 19 58
Plugging completed November 26, 19 58
Reason for abandonment of well or producing formation No production

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 180' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to surface, squeezed in 100 sacks of cement

Pressure-Circulating 100
Minimum
Maximum 250

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1958

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 24 1958

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Paul E. Gathers (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul E. Gathers

(Address)


SUBSCRIBED AND SWORN to before me this 10th. day of December, 19 58

My commission expires May 17, 1962

Mildred Jean

Notary Public.

PLUGGING
FILE SEC 26 T 11 R 16w
BOOK PAGE 4 LINE 6



15-051-01215-0000

DRILLER'S WELL LOG

Davis Bros.-Transit Corporation - Shaw "B" # 1 located in
NE NE NE Sec. 26-11S-16W
Ellis County, Kansas

Commenced: November 13, 1958
Completed: November 26, 1958
Elevation: 1756 KB

Casing 8 5/8" @ 180'
Cemented w/150 sacks

| <u>Formation</u> | <u>From</u> | <u>To</u> |
|--------------------------|-------------|-----------|
| Surface clay | 0 | 35 |
| Sand | 35 | 55 |
| Shale and shells | 55 | 170 |
| Shale | 170 | 300 |
| Sand | 300 | 390 |
| Shale | 390 | 590 |
| Pyrite | 590 | 592 |
| Shale | 592 | 617 |
| Pyrite | 617 | 620 |
| Shale and Pyrite streaks | 620 | 680 |
| Red bed | 680 | 911 |
| Anhydrite | 911 | 942 |
| Shale and shells | 942 | 1590 |
| Lime and shale | 1590 | 1795 |
| Lime | 1795 | 2025 |
| Shale w/lime streaks | 2025 | 2050 |
| Lime and shale | 2050 | 2510 |
| Lime | 2510 | 2595 |
| Lime and shale | 2595 | 2728 |
| Lime | 2728 | 2761 |
| Lime and shale | 2761 | 2820 |
| Lime and shale streaks | 2820 | 2870 |
| Lime | 2870 | 2925 |
| Lime and shale streaks | 2925 | 2989 |
| Lime and shale | 2989 | 3010 |
| Lime | 3010 | 3208 |
| Lime and shale | 3208 | 3263 |
| Lime | 3263 | 3330 |
| Lime and chert | 3330 | 3343 |
| Lime | 3343 | 3358 |
| Lime conglomerate | 3358 | 3404 |
| Lime | 3404 | 3447 TD |

Summary of Formation

| | |
|---------------|-------|
| Anhydrite | 909' |
| Topeka | 2678' |
| Heebner | 2924' |
| Toronto | 2945' |
| Lansing | 2971' |
| Base of KC | 3217' |
| Conglomerate | 3294' |
| Simpson Dolo. | 3370' |
| Arbuckle | 3399' |

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

Subscribed and sworn to before me
this 10th. day of December, 1958.

TRANSIT CORPORATION

BY Paul E. Gathers

My Commission expires May 17, 1962.

Notary Public

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 26 T. 11 R. 16W
BOOK PAGE 4 LINE 6