

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR George R. Jones API NO. 15-007-21,327-000
 ADDRESS 125 N. Market, Suite 1210 COUNTY Barber
Wichita, Kansas 67202 FIELD _____
 **CONTACT PERSON George R. Jones LEASE Lawrence
 PHONE 316-262-5503

PURCHASER _____ WELL NO. #3
 ADDRESS _____ WELL LOCATION 300' E. NE SW
 _____ Ft. from _____ Line and
 _____ Ft. from _____ Line of
 the SEC. 35 TWP. 32S RGE. 10W

DRILLING CONTRACTOR BEREDCO INC.
 ADDRESS 401 E. Douglas, Suite 402
Wichita, Kansas 67202

PLUGGING CONTRACTOR Halliburton Services
 ADDRESS 410 Union Center, Wichita, KS 67202

TOTAL DEPTH 4470' PBTD _____
 SPUD DATE 12/21/81 DATE COMPLETED 12/31/81
 ELEV: GR 1412' DF _____ KB 1417'



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

KCC
 KGS

MISC. _____

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(MUD)~~ TOOLS (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	20#	372'	Class H	275	2% Gel, 3% CC

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated

TEST DATE:		PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water % bbls.
Disposition of gas (vented, used on lease or sold)	Producing interval(s)		

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum _____ Depth _____
 Estimated height of cement behind pipe _____

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			LOG TOPS: KB 1417'	
Red Bed	0'	724'	Heebner	3412 (-1995)
Red Bed & Shale	724'	1300'	Douglas Ss	3477 (-2060)
Lime & Shale	1300'	4395'	Lansing	3705 (-2288)
Lime	4395'	4470'	Kansas City	3937 (-2520)
			Stark Shale	4105 (-2688)
			B/KC	4167 (-2750)
			Cherokee Shale	4315 (-2898)
			Miss. Chat	4385 (-2968)
			TD	4475 (-3058)
			DTD	4470 (-3053)
Total Rotary Depth 4470'				
DST #1: 4356 - 4405 30" 45" 60" 60" weak blow; rec. 65' mud ifp 84 - 84 ffp 84 - 84 isip 116 fsip 243 hyd. 2141 - 2121 temp. 122°				
DST #2: 4404 - 4421 30" 45" 60" 60" fair blow; rec. 30' mud with few oil specks; & 185' muddy water ifp 105 - 105 ffp 158 - 169 isip 1353 fsip 1311 hyd. 2162 - 2142 temp. 123°				
Plugged with 60 sacks @ 650'; 40 sacks @ 360'; 10 sacks @ 40'-0; 10 sacks RH; 5 sacks MH. State Supervisor: Morris Lesley				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

George R. Jones OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS xxFORX OPERATOR OF THE Lawrence LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. #3 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 31st DAY OF December 19 81, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) *George R. Jones*
 George R. Jones

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6th DAY OF January 1982

Wilma E. Clark
 NOTARY PUBLIC
 Wilma E. Clark

MY COMMISSION EXPIRES: August 5, 1984

