

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 1 Twp. 13 Rge. 16 (E) (W) x  
Location as "NE/CNWxSWx" or footage from lines SW SW SE

Lease Owner Petroleum Management Inc.  
Lease Name Perschisnke Well No. #6  
Office Address 1515 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 6-14-66 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6-15-66 19\_\_\_\_  
Plugging completed 6-17-66 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3343' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 3320', mixed and ran 5 sacks cement thru dump hauler.  
Mudded hole to 500', set 25' rock bridge. Dumped 6 yards ready-mix from 475' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
6-21-1966  
JUN 21 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 20 day of June, 1966  
Sidney J. Miller  
Notary Public.

My commission expires 24 October 1968



15-051-02016-00-00

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

JCF


Company ANSCHUTZ DRILLING COMPANY, INCE.  
Farm: Porschisnke No. 6

SEC. 1 T. 13 S. 16W  
SW SW SE

Total Depth. 3340 Rot. Bushing  
Comm. 4-1-50 Comp. 4-12-50  
Shot or Treated.  
Contractor. Strain Drilling Co.  
Issued. 5-20-50

County. Ellis

KANSAS



CASING:  
8 5/8" 960' cem w/450 sx  
5 1/2" 3332' cem w/125 sx

Elevation. 1924 DF

Production.

Figures Indicate Bottom of Formations.

clay, soil	60
post rock, shale	130
shale, shells	440
sand, shale	460
pyrite, shale	500
shale, shells	590
sand	620
shale, shells, sand	750
shale, red bed	973
anhydrite	1020
shale, shells	1380
salt, shale	1680
shale, lime	1923
lime	2085
shale, lime	2370
shale, shells	2425
shale, lime	2890
lime	3332
sand, lime	3334
free oil	3340 R.B.
Total Depth	

RECEIVED  
STATE CORPORATION COMMISSION  
7-22-1966  
JUL 22 1966  
CONSERVATION DIVISION  
Wichita, Kansas

Tops:	
Anhydrite	973
Topeka	2790
Heebner	3017
Kansas City	3089 ?
Arbuckle	3334

D.S.T. 3334-40 recovered 125'  
muddy oil. Tool open 1 hr.  
Bottom hole pressure 650#.