

15-051-23021-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 1 TWP. 13 RGE. 16 ~~XX~~W
Location as in quarters or footage from lines:
C E/2 SW/4 SW/4

Lease Owner Roy Vonfeldt
Lease Name MARY SCHMITT Well No. A #1
Office Address 524 St. John Russell, KS 67665
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed 6-6-82
Application for plugging filed 6-6-82
Plugging commenced 6-6-82
Plugging completed 6-6-82
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ bottom _____ T.D. 3421'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Bottom Plug: @ 660' w/70 sacks cement thru drill pipe
Middle Plug: @ 300' w/40 " " " " "
Top Plug: @ 40' w/1/2 sack hulls & 10 sacks cement
10 sacks cement in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1982
6-14-1982
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (employee of owner) or ~~(owner)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
P.O. Box 823 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of June, 1982
Blondy M. Deane
Notary Public



DRILLERS WELL LOG

DATE COMMENCED: May 30, 1982
DATE COMPLETED: June 6, 1982

Roy Vonfeldt
MARY SCHMIDT A-1
C E/2 SW SW
Sec. 1, T13S, R16W
Ellis County, Ks.

0 - 1055'	Surface Soil, Red Bed, Shale, Shells
1055 - 1090'	Anhydrite
1090 - 2856'	Shale & Lime
2856 - 2865'	Shale & Sand
2865 - 3087'	Lime
3087 - 3108'	Shale
3108 - 3137'	Lime & Shale
3137 - 3412'	Lime
3412 - 3421'	Dolomite
3421'	RTD

FORMATION DATA

Anhydrite	1055'
Severy	2856'
Topeka	2865'
Heebner	3087'
Toronto	3108'
Kansas City	3137'
Base K.C.	3373'
Arbuckle	3412'
RTD	3421'

ELEVATION: 1965 K.B.

Surface Pipe: Set new 8-5/8",
2 1/2" pipe @277' w/165 sacks
60/40 pozmix, 2% gel, 3% cc.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 9th day of June 1982.

Dorothy M. Blake
Notary Public



RECEIVED
STATE CORPORATION COMMISSION
6-14-1982
JUN 14 1982

CONSERVATION DIVISION
Wichita, Kansas