


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Russell County Sec. 10 Twp. 13 Rge. 14 (E) (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NW SE
Lease Owner Great Lakes Carbon Corp
Lease Name H. Krug Well No. 1
Office Address 501 Pet. Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-14 19 48
Application for plugging filed 2-14 19 48
Application for plugging approved 2-14 19 48
Plugging commenced 2-14 19 48
Plugging completed 2-14 19 48
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Straugh, Hays, Kansas
Producing formation None Depth to top - Bottom Total Depth of Well 3350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		NONE				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated heavy mud through drill pipe

From 3350 to 470

Placed plug at 470

Cement 410 to 435 15 sacks

Heavy mud 435 to 170

Plug at 170

Cement 170 to 150 10 sacks


Heavy mud 150 to 25

Cement 25 to 6 10 sacks

6 to 0 cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Great Lakes Carbon Corp
Address 501 Pet. Building, Wichita 2, Kansas



STATE OF _____, COUNTY OF _____, SS.

(employee of owner) or (owner or operator) of the above-described well
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) *P. N. Sholtz*
501 Petroleum Bldg, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of February, 1948
My commission expires November 8, 1950
Notary Public.



PLUGGING
FILE SEC 10 T 13 R 14
BOOK PAGE 14 LINE 33

15-167-00436-00-00

WELL LOG - H.KRUG #1

Great Lakes Carbon Corp
H. Krug #1
Total Depth 3350
Comm. 2-1-48
Contractor - Glenn Peel
Drilling co., Inc.
Hoisington, Kansas

NW NW SE
Section 10-13S-14W
Russell Co., Kansas
Elevation 1812
Casing 8 5/8-466-250
Cement circulated

0	-	30	Surface Lime
30	-	225	Lime, Sand & Shale
225	-	280	Shale & Shells
280	-	370	Shale & Sand
370	-	395	Iron
395	-	466	Shale, Shells & Sand
466	-	540	Shale
540	-	600	Shale & Red Bed
600	-	685	Red Bed
685	-	845	Anhydrite
845	-	880	Shale & Shells
880	-	940	Sandy Red Bed
940	-	1160	Shale & Shells
1160	-	1485	Shale & Lime
1485	-	1580	Lime & Shale streaks
1580	-	1680	Lime & Shale
1680	-	1865	Lime & Shale streaks
1865	-	1920	Lime & Shale
1920	-	2065	Lime
2065	-	2130	Lime & Shale
2130	-	2275	Shale & Lime streaks
2275	-	2370	Shale & Shells
2370	-	2440	Lime
2440	-	2455	Lime & Shale
2455	-	2550	Shale & Lime streaks
2550	-	2640	Shale
2640	-	2652	Lime & Shale
2652	-	2710	Lime
2710	-	2780	Lime
2780	-	2835	Broken lime
2835	-	2915	Lime
2915	-	3350	Total Depth

Top Lansing - KC 2971
Top Arbuckle 3287

FEB 24 1948
02-24-1948

PLUGGING
FILE SEC 10 T 13 R 14W
BOOK PAGE 14 LINE 33