

WELL PLUGGING RECORD

	+	

Russell County. Sec. 5 Twp. 13S Rge. 14W (E) (W)

Location as "NE/CNW¼SW¼" or footage from lines C NW NW SE
Lease Owner Peel-Hardman Producers
Lease Name Foster Well No. 1
Office Address P.O. Box 359, Hoisington, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 27 1949
Application for plugging filed April 27 1949
Application for plugging approved April 27 1949
Plugging commenced April 27 1949
Plugging completed April 27 1949
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?..... Yes.....

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... 3159 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

3159'	-	251 $\frac{1}{2}$ '	-	Heavy Rotary Mud
251 $\frac{1}{2}$ '	-	250'	-	Wooden Plug
250'	-	212 $\frac{1}{2}$ '	-	15 sacks cement
212 $\frac{1}{2}$ '	-	31 $\frac{1}{2}$ '	-	Heavy Rotary Mud
31 $\frac{1}{2}$ '	-	30'	-	Wooden Plug
30'	-	6'	-	10 sacks cement
6'	-	Surface	-	Cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....
Address.....


STATE OF Kansas, COUNTY OF Barton, ss.
Glenn Peel Drilling Co., Inc. (employee of owner) or ~~(owner or operator)~~ of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN PEEL DRILLING COMPANY, INC.

(Signature) BY: J.B. [Signature]
P.O. Box 359, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of April, 1949

My commission expires..... June 4, 1951

.....
Notary Public.



15-167-00351-00-00

DRILLER'S LOG

Company: Peel-Hardman Producers

Sec. 5 Twp. 13S Rge. 14W
C NW NW SE

Farm: Foster Well No. 1

County: Russell,
Kansas

Total Depth: 3159'

Comm.: 4-18-49 Comp.: 4-27-49

Elevation:

Contractor: Glenn Peel Drilling Co., Inc.

Production: Dry

Casing:

8 5/8" 720' cem.

Figures below indicate bottom of formations

Shale and Shells	0 -	105
Shale and Streaks of Red Rock		230
Sand and Shale		285
Shale Streaks and Pyrite		307
Iron		319
Shale, Sand, Streaks of Pyrite		410
Red Bed and Shells		711
Anhydrite		750
Shale and Shells		985
Salt and Shale		1065
Shale and Salt		1350
Shale and Lime		1515
Lime		1925
Lime and Shale		2050
Shale and Lime Streaks		2570
Lime		3159
Total Depth		3159

05-03-1949

This is to certify that the above information is, to the best of our knowledge, true and correct.

GLENN PEEL DRILLING COMPANY, INC.

BY: *J. B. [Signature]*

SUBSCRIBED AND SWORN to before me this 30th day of April, 1949

My commission expires June 4, 1951

Marian M. Herbert
Notary Public

