

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-22,413-00-00

LEASE NAME Boxberger

WELL NUMBER 1

SPOT LOCATION W/2 W/2 NE

SEC. 1 TWP. 13 SRGE. 14 ~~XXXX~~(W)

COUNTY Russell

Date Well Completed 7-08-84

Plugging Commenced 7-08-84

Plugging Completed 7-08-84

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70, Hays, KS 67601

PHONE # (913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 2935' RTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		-0-	377'	8 5/8"	377'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mud laden fluid 2935' - 680'
100 sks cement @ 680'
40 sks cement @ 200'
10 sks cement @ 40'
10 sks cement @ Rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and

correctly and truthfully reported.

(Signature) Joe K. Branum

P. O. Box 506

(Address) Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 10th day of July, 1984

DENISE S. REYNOLDS
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires:
2-13-85

My Commission expires: February 13, 1985

Denise S. Reynolds, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1984
07-11-1984
CONSERVATION DIVISION
Wichita, Kansas

15-167-22413-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: DaMar Resources, Inc.
P. O. Box 70
Hays, KS 67601

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Boxberger WELL: #1

LOCATION: W/2 W/2 NE
Section 1-13S-14W
Russell County, Kansas

ROTARY TOTAL DEPTH: 2935'

ELEVATION:

COMMENCED: 7-03-84

DATE COMPLETED: 7-08-84

CASING: 8 5/8" @ 377' with 225 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	30'	Shale	1760'
Sand & Shale	208'	Shale & Shells	2171'
Sandstone & Pyrite	310'	Shale	2569'
Shale	647'	Shale & Lime	2857'
Anhydrite	680'	Lime & Shale (RTD)	2935'
Sand & Shale	1336'		

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)



Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.




Joe K. Branum

Subscribed and sworn to before me this 10th day of July, 1984.

My Commission Expires: February 13, 1985.





Denise S. Reynolds, Notary Public