

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Russell County. Sec. 5 Twp. 13S Rge. 11 (EX) (W)

Location as "NE/CNW%SW%" or footage from lines SW/4 SW/4 SE/4

Lease Owner Veeder Supply and Development Co.

Lease Name Foster Well No. 1

Office Address P. O. Box 201, Cherryvale, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 27 19 55

Application for plugging filed March 27 19 55

Application for plugging approved March 27 19 55

Plugging commenced March 27 19 55

Plugging completed March 27 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Great Bend, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3266 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	217'	Cemented w/125 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole with Halliburton plug at 210', 1/2 sack hulls, 20 sacks cement; filled with mud to 35', plug at 35', 1/2 sack hulls, 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply and Development Co.
Address P. O. Box 201, Cherryvale, Kansas

STATE OF Kansas COUNTY OF Montgomery ss.
Floyd W. Hild (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Floyd W. Hild

Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of March 19 55

My commission expires July 11, 1956

Notary Public
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 5 T 13 R 14 W
BOOK PAGE 107 LINE 30

APR 04-01-1955
CONSERVATION DIVISION
Wichita, Kansas

15-167-04798-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Veeder Supply & Dev'l. Co. -Allan Melhado, et al Farm Foster No. 1 Depth 3266'
 Contractor Veeder Supply & Dev'l. Co. Pipe 217' 8 5/8" csg. cemented w/125 sacks cement
 Location SW/4 SW/4 SE/4 Sec. 5 Twp. 13S Range 14W
 Commenced 3-15-1955 Completed 3-27-1955 County Russell State Kansas

Shale and lime shells	0	120	120	TOPS:		
Sandy shale	120	150	30			
Shale	150	215	65	Topeka	2701	-897
Shale and shells	215	380	165	Heebner	2926	-1122
Sand and shale	380	540	160	Toronto	2948	-1144
Red bed, shale	540	835	295	Lansing	2979	-1175
Anhydrite	835	876	41	Base KC	3217	-1413
Shale and shells	876	1470	594	Arbuckle	3262	-1458
Shale, shells, lime streaks	1470	1540	70			
Lime and shale	1540	1935	395			
Shale and lime streaks	1935	2245	310			
Shale and lime	2245	2440	195			
Shale, lime shells	2440	2650	210			
Lime and shale	2650	2850	200			
Lime	2850	3266	416			
Total Depth	3266					

Dry and abandoned

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

Floyd W. Hild, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and on oath hereby states that the above drilling log covering the Foster #1 Well located in Section 5-13s-14W. Russell County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By Floyd W. Hild
Floyd W. Hild

Subscribed and sworn to before me this 30th day of March, 1955.

Coler Lawson
Notary Public

My commission expires July 11, 1956.

PLUGGING
FILE SEC. 5 T/3 R/4W
BOOK PAGE 107 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1955
CONSERVATION DIVISION
Wichita, Kansas