


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15-051-00642-00-00  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County. Sec. 2 Twp. 11S Rge. (E) 17.(W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE SE NE  
Lease Owner Isern Drilling Company et al  
Lease Name Slimmer Well No. 1  
Office Address Box 92, Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-5-51 19  
Application for plugging filed 11-5-51 19  
Application for plugging approved 11-5-51 19  
Plugging commenced 11-5-51 19  
Plugging completed 11-5-51 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3489' Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
	Surface Pipe	0	222	8-5/8	222	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud topped with bridge and wood plug @ 220'. Cemented with twenty sacks cement. Set bridge and wood plug at 40'. Cemented with ten sacks, cement returning to base of cellar.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. W. Keyes Drilling Co.  
Address Box 92, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
I, Edw. H. Isern, Part Owner (employee or owner or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edw H Isern  
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of November, 19 51

George A Meyer  
Notary Public.

My commission expires Feb. 10, 1955.

PLUGGING  
FILE SEC 2 11-1122  
BOOK PAGE 122 28

WELL LOG

15-051-00642-00-00

ISERN DRILLING COMPANY et al, OWNERS - Slimmer #1  
 SE $\frac{1}{4}$  SE $\frac{1}{4}$  NE $\frac{1}{4}$  Section 2, Township 11S, Range 17W.  
 Ellis County, Kansas

Elevation: 1901' DF	Figures indicate bottom of formation
Pipe Record	0 to 222 shale and lime
3-5/8" set @ 222'	330 shale and shells
	360 sand
	450 shale and shells
	525 sand
	564 pyrite
Tops - RBM	620 shale and shells
	770 sand
Heebner 3060 (-1157)	910 shale and shells
Lansing 3101 (-1198)	1030 sand and shale
Base K. C. 3363	1095 shale and shells
Conglomerate 3376 (-1473)	1135 anhydrite
Simpson 3443 (-1540)	1500 shale and shells
Arbuckle 3483 (-1580)	1645 salt
	1740 shale and shells
	2832 <del>lime &amp; shells</del>
	2840 shale and shells
	3120 lime and shale
	3376 lime
	3483 conglomerate
	3489 lime
	3489 Total Depth D & A

STATE OF KANSAS )  
 COUNTY OF BARTON ) SS

I, M. M. Shropshire, Part Owner, of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 10th day of November, 1951.

George A Meyer  
 Notary Public

My commission expires Feb. 10, 1955.

FILE 2 11 17W  
 BOOK PAGE 122 28

RECEIVED  
 STATE OF KANSAS  
 11-13-1951  
 NOV 13 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas