

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21,184-00-00

245 North Water
Wichita, KS 67202

Operator's Full Name Dreiling Oil, Inc.

Complete Address Rt. # 1, Victoria, Kansas 67671

Lease Name Boxberger Well No. B 1

Location SW SE NE Sec. 1 Twp. 13S Rge. 14 (~~EAST~~) (West)

County Russell Total Depth 3168'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co Tools & Allied Cementing Co.

Address Rt. #1, Victoria, Kansas 67671 License No. _____

Operation Completed: Hour: 11:30 AM Day: 19 Month: 12 Year: 19 80

The above well was plugged as follows:

Sanded back to 2815' and 4 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 5 sx hulls, 25 sx mud-gel, plug, and 100 sx cement.

Recovered aprox. 2350' of 4 1/2" casing.

Plugged back to 2960'.

Top perforation at 2861'

3167' of 4 1/2" casing cemented with 125 sx cement.

167' of 8 5/8" surface casing cement circ.

DEC 27 1980

12-23-1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: *Deanne J Rankin*
Conservation Division Agent

INVOICED

1-12-81

3857-W