

15-167-00300-00-00

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW-SW-NE

SEC. 8 TWP. 13 RGE. 14W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Mollinger

Operator Shields Oil Producer Address Russell, Kans.

Field \_\_\_\_\_ County Russell

Total Depth 3297' Feet.

Plugging Contractor Shields Oil Producer

Plugging Contractor's License No. 160

Address Russell, Kans.

(Describe briefly the manner in which the well was plugged)

*Surface pipe - Non. 5 1/2" @ 3276', 7" @ 3008', 8" @ 2446',  
10" @ 852', 12 1/2" @ 540' & 15 1/2" @ 341'. Started 5 1/2"  
casing when free stopped & filled w/ heavy mud. Same  
procedure on all the casing. Started 15 1/2" then mud  
to 300' from top, set plug, rock bridge & 60 sq. cen.  
w/ dump trailer. Then pulled rest of 15 1/2" casing out &  
mud to 35' from top, set plug, rock bridge, & 30 sq. cen.  
to base of cellar.*

*Milton Gahart*  
District Conservation Agent

Date 10-14-1955

STATE CORPORATION COMMISSION

OCT 17 1955  
10-17-1955  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC. 8 T. 13 R. 14W  
BOOK PAGE 9 LINE 5