

15-051-05654-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
4-10-1972  
APR 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address Boz 308 Ellinwood, Kansas 67526

Lease Name Slimmer Well No. 8

Location SW NE NW Sec. 2 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3465'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor        Co. Tools by HOWCO

Address        License No.       

Operation Completed: Hour 2 P Day 7 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3465' 8 5/8 csg set at 120' cwc 75 sk. (Cmt. Mat. Halco-Light)

5 1/2 csg set at 3463' cw 150 sk cmt.

5 1/2 csg PBTD 3415' with perf. (3387-3390) No pipe recovered.

Ran 104 jts tbg set at 3175' -pumped 25 sk gel & water W/100 lbs hulls -displaced

25 sk cmt. Pulled 90 jts tbg set at 420' -circ 40 sk cmt to surface. -Pulled

remaining 14 jts tubing and capped 5 1/2 csg W/5 sk cmt.

Pumped 50 sk cmt down anulus with 150 lbs pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 4-11-72

INV. NO. 5510-W