

15-051-05407-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
4-14-1972  
APR 14 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Slimmer Well No. 7

Location NW NW NW Sec. 2 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3645'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by HOWCO

Address        License No.       

Operation Completed: Hour 12:30 P Day 13 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3645' 8 5/8 csg set at 160' cwc 110 sk. Cmt. Mat. "Halco-light"

5 1/2 csg set at 3645' cw 125 sk cmt. & perf. (3535-3557)

5 1/2 csg squeezed at 910' W/275 sk cmt.

Ran 104 jts tgb set at 3175' -pumped 25 sk gel & water W/100 lbs hulls, -displaced

25 sk cmt. -Pulled 85 jts tgb set at 570' -circ 55 sk cmt to surface. Pulled

remaining 19 jts tgb & capped 5 1/2 csg W/5 sk cmt.

Pumped 15 sk cmt down annulus with 75 lbs pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Z. Massey  
Well Plugging Supervisor

DATE 4/12/72  
INV. NO. 5356-W