

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15- (none)

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Champlin Petroleum Co.

Complete Address P.O. Box 9367 Forth Worth, Texas 76107

Lease Name Slimmer Well No. 6

Location NE SE NW Sec. 2 Twp. 11 Rge. 17 (East) (West)

County Ellis Total Depth 3892'

Abandoned Oil Well      Gas Well      Input Well      SWD Well XXX D&A     

Other well as hereinafter indicated Start of a sink hole.

Plugging Contractor Champlin Petroleum Co.

Address P.O. Box 9367 Forth Worth, Texas 76107 License No.     

Operation Completed: Hour: 9:15 AM Day: 28 Month: Jan. Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part      None     

The above well was plugged as follows:

10 3/4"-160' S.P. cuc. with 100 sacks common. 6 5/8" set at 3835' cuc. with 1333 sacks common. 4 7/8" Bit, 2--3 1/2" drill collars and 590' of 2 7/8" tubing stuck in hole at 650'. Pumped into 2 7/8" tubing with pump truck.

Jan. 25-82 Pumped in 500 sacks common cement.

Jan. 26-82 pumped in 300 sacks 50/50 posmix 6% Gel.-3% Cal.Cl. and pumped between tubing and 6 5/8" casing 60 sacks Gel. and 300 sacks 50/50 posmix 3% Gel.-3% Cal..

Jan. 27-82 pumped in 500 sacks Halliburton Light with 5 pounds Gilsonite and 1/4 pound Flo-cele per sack.

Jan. 28-82 Filled to top with 25 sacks Halliburton Light 1/4 pound Flo-Cele.

Amount of Surface Casing: 160' of 10 3/4"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION

FEB -

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 2-8-82  
INV. NO. 9266-W

Signed:      Conservation Agent

RECEIVED  
STATE CORPORATION COMMISSION  
2-2-1982  
FEB - 2 1982

CONSERVATION DIVISION  
Wichita, Kansas