

15-051-05406-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-10-1972
APR 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67626

Lease Name Slimmer Well No. 5

Location SE NE NW Sec. 2 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3495'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 6:30 P Day 6 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3495' 8 5/8 csg set at 158' cwc 100 sk. Cmt. Mat. Halco-Light.

5 1/2 csg set at 3495' cw 200 sk cmt.

5 1/2 csg PBTB 3200' with perf. (3180-3185) No pipe recovered.

Ran tbg (100 jts) set at 3050' -pumped 25 sk gel & water W/100 lbs hulls -displaced

25 sk cmt. -pulled 86 jts tbg set at 420' -circ 40 sk cmt to surface. -pulled

remaining 14 jts tbg ~~XXX XX XXX~~ - Capped 5 1/2 csg W/5 sk cmt.

Pumped 50 sk cmt down annulus with 300 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben F. Massey
Well Plugging Supervisor

INVOICED

DATE 4-11-72

INV. NO. 5509-W