

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-10-1972
APK 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Slimmer Well No. 3

Location NE ~~NE~~ NW Sec. 2 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3533'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 11 A Day 6 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3533' 8 5/8 csg set at 167' cwc 100 sk. Cmt. Mat. Halco-Light

6 1/2 csg set at 3533' cw 159 sk cmt.

5 1/2 csg PBD 3400' with perf. (3222-3242) Model "D" packer set at 3197' No pipe recov.

Ran 100 jts tbg set at 3050' -pumped 25 sk gel & water W/100 lbs hulls -displaced

25 sk cmt. -Pulled 85 jts tbg set at 450' -circ 45 sk cmt to surface.

Pulled remaining 15 jts tbg -Gapped 5 1/2 csg W/5 sk cmt.

Pumped 50 sk cmt down annulus. 300 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Murrey
Well Plugging Supervisor

INVOICED

DATE 4-11-72

INV. NO. 5508-W