

KANSAS

15-051-05403-00-00

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
4-11-1972
APR 11 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Slimmer Well No. 1

Location NW NE NW Sec. 2 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3487'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 1 P Day 10 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3487' 8 5/8 csg set at 149' cwc 100 sk. Cmt. Mat. "Halco-Light"

4 1/2 Csg set at 3484' cw 200 sk cmt.

4 1/2 csg PBTD 3449' with perf. (3186-3203)

4 1/2 csg squeezed at 767' W/320 sk cmt. No pipe recovered.

Ran 100 jts tbg set at 3050' -pumped 20 sk gel & water W/100 lbs hulls, -displaced

20 sk cmt. Pulled 85 jts tbg set at 450' -circ 35 sk cmt to surface. Pulled

remaining 15 jts tbg and capped 4 1/2 csg W/5 sk cmt.

Pumped 10 sk cmt down anulus W/200 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo F. Massey*
Well Plugging Supervisor

INVOICED

DATE 4/13/72

INV. NO. 5531-W