

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
4-14-1972
APR 14 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company
Complete Address Box 308 Ellinwood, Kansas 67526
Lease Name C. E. Slimmer Well No. 2
Location NE NW NW Sec. 2 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3510'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools by HOWCO
Address License No.
Operation Completed: Hour 11 A Day 11 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3510' 8 5/8 csg set at 153' cwc 100 sk. Cmt. Mat. "Halco-Light"
5 1/2 csg set at 3507' cw 200 sk cmt.
5 1/2 csg PBSD 3471' with perf. (3194-3220) No pipe recovered.
Limit plug set at 2850' cw 2 sk calseal & 2 sk cmt.
Ran 95 jts tbg set at 2850' -pumped 22 sk gel & water W/100 lbs hulls -displaced
25 sk cmt. -Pulled 80 jts tbg set at 450' -circ 40 sk cmt to surface. Pulled
remaining 15 jts tbg -capped 5 1/2 csg W/5 sk cmt.
Pumped 10 sk cmt down annulus with 700 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/17/72
INV. NO. 5358-W