

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -051 -21,676 (of this well)

Operator's Full Name E S P Development, Inc. c/o Lewis Eulert

Complete Address Paradise, Ks.

Lease Name Delmar Chrisler Well No. 1

Location SE SE SE Sec. 35 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3495'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Emphasis Drlg.

Address Russell, Ks. License No.

Operation Completed: Hour 9:30 P Day 19 Month 4 Year 1979

The above well was plugged as follows:

RTD 3495' 8 5/8 csg set 273' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thrudrill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
4-23-1979
APR 23 1979

I hereby certify that the above well was plugged as herein stated. Wichita, Kansas

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 4-24-79
INV. NO. 9474. W