

15-051-20871-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1-31-1973  
JAN 31 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Kaiser-Francis

Complete Address 4120 E. 51st Street Tulsa, Oklahoma

Lease Name Love Well No. 1

Location SW SW SE Sec. 1 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3060'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling

Address Wichita, Kansas License No.       

Operation Completed: Hour 11 A Day 28 Month 1 Year 1973

The above well was plugged as follows:

RTD 3060' 8 5/8 csg set at 194' CWC Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Loz Murray  
Well Plugging Supervisor

DATE 1/31/73  
INV. NO. 6930-W