

15-051-02077-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tomlinson Oil Co., Inc.

Complete Address 1125 Wichita Plaza Wichita, Kansas 67202

Lease Name Nielson Well No. 4

Location SW NW SW Sec. 28 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3410

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers Inc.

Address Box 486 Ellinwood, Kansas License No. 462

Operation Completed: Hour 11 A Day 24 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 3410' 8 5/8 csg set at 982' cwc 475 sk.

5 1/2 csg set at 3410' cw 100 sk cmt.

5 1/2 csg PBTD 3355' and perf. (3336-3344)

Filled 5 1/2 csg W/sd (3330-3355) Dumped 5 sk cmt W/dump bailer. (3290-3330)

Cutoff and recovered 2730' of 5 1/2 csg.

Set 8 5/8 wood plug at 450' Rock bridge (430-450) Filled to surface with 6 yds

readymix cmt. (0-430)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/26/70
INV. NO. 1305-W

Signed: Bio R. Massey
Well Plugging Supervisor