

15-051-00296-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 24 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Tomlinson & Kathol
Complete Address: 1125 Wichita Plaza Wichita, Kans
Lease Name Nielsen Well No. 1
Location SE NW SW Sec. 28 Twp. 11 Rge. (E) (W) 16
County Ellis Total Depth 3400
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kans License No. 436
Operation Completed: Hour 6PM Day 20 Month 11 Year 64

The Above well was plugged as follows:

8 5/8" 155' circulated with cement - 5 1/2" 3400' with 100 sax cement
PB 3338' - Perf 3331

Filled with sand to 3320', set 4 sax cement with dump bailer,
pulled 2800' 5 1/2" to 360' - circulated hole with heavy gel mud (33 sax Gel)
through 5 1/2" - pulled pipe to 400' - displaced 25 sax cement through 5 1/2" -
pulled pipe to 180', displaced 25 sax cement through 5 1/2" - heavy mud to
35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/25/64
INV. NO. 206-W

Signed: Eldon Petty
Well Plugging Supervisor