

15-051-02075-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1970
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tomlinson Oil Co., Inc.

Complete Address 1125 Wichita Plaza Wichita, Kansas 67202

Lease Name Nielson Well No. 2

Location NW NW SW Sec. 28 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3400'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers Inc.

Address Box 486 Ellinwood, Kansas License No. 462

Operation Completed: Hour 10:15A Day 27 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 3400' 8 5/8 csg set at 149' cwc

5 1/2 csg set at 3398' cw 150 sk cmt.

5 1/2 csg PBTD 3342' and perf. (3177-3179) and (3345-3342)

5 1/2 csg DV tool set at 945' cwc to surface. 450 sk.cmt.

No pipe recovered.

Filled 5 1/2 csg W/sd (3160-3342) Dumped 5 sk cmt W/dump bailer. (3120*3160)

Mud to 450' set 5 1/2 plug&rock (420-450) readymix cmt (0-420) 2 1/2 yds.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo D. Messing
Well Plugging Supervisor

DATE 1/30/70
INV. NO. 1333-W