

15-051-02078-0000

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Tomlinson Oil Co., Inc.

Complete Address 1125 Wichita Plaza Wichita, Kansas 67202

Lease Name Nielson Well No. 5

Location SW SW NW Sec. 28 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3375

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Pipe Pullers Inc.

Address Box 486 Ellinwood, Kansas License No. 462

Operation Completed: Hour 9:30A Day 27 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 3375' 8 5/8 csg set at 945' cwc 475 sk

5 1/2 csg set at 3372' cw 100 sk cmt.

5 1/2 csg PBTD 3350' and perf. (3284-3300)

Filled 5 1/2 csg W/sd (3275-3350) Dumped 5 sk cmt W/dump bailer. (3235-3275)

Cutoff and recovered 2705' of 5 1/2 csg.

Mud to 450' set 8 5/8 plug, rock bridge (430-450) readymix cmt (0-430)

I hereby certify that the above well was plugged as herein stated.

Signed: Ben J. Marney  
Well Plugging Supervisor

INVOICED

DATE 1/30/70

INV. NO. 1335-W