



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
 STATE CORPORATION COMMISSION

MAY 13 1959
 05-13-59
 CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date May 7, 1959, 19 , authorized the following plugging operation:

Operator's Full Name: Twin Drilling Co.

Complete Address: 1005 Central Bldg., Wichita, Kans.

Lease Name: Campbell Well No. 1

Location: NW NW NW Sec. 33 Twp. 28 Rge. 15 (E) (W) X

County: Pratt Total Depth: 4935

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

343' of 8 5/8" surface casing circulated with cement. Fill hole
to 325' with heavy drilling mud. Set cementing plug at 325' and
pour 20 sack cement through drill pipe. Heavy mud to 35'. Set a
cap plug at 35' with cement to base of casing.

Very truly yours,

Signed: [Signature]
 Conservation Division Agent