

State of Kansas



15-051-20081-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
7-3-1967
JUL 3 1967
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drlg. has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg. Co

Complete Address: 801 Union Center Wichita Kansas

Lease Name: Befort Well No. 1

Location: Ne Se Sec. 1 Twp. 11 Rge. 17 (E)(W)

County Ellis Total Depth 3485 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Cook was instructed to plug the well as follows:

~~Jet pumps circulate hole with heavy mud, set cementing plug at 540 ft.,
and displace 15 sack cement thru drill pipe, heavy mud to 250 ft., set
cementing plug and displace 15 sack cement thru drill pipe, heavy mud
to 40 ft., set cementing plug, false hulls and 10 sack cement, cementing
to base of cellar.~~

Very truly yours,
Gilbert P. Leiker
Gilbert P. Leiker
Conservation Division Agent