

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. art Hunt of Buffalo Wdg Co. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Clammar del company

Complete Address: 2707 Vine St #8 - Hays, Kans. 67601

Lease Name: Harry M. Milson Well No. #1

Location: 200's - SW - SW - NW Sec. 28 Twp. 11^S Rge. 16^W (E) (W)

County: Ellis Total Depth: 3301^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Hunt was instructed to plug the well as follows:

- 8 5/8" 931^{FE} SP. euc w/ 120ST 60/40 Permud - 2% Gel. 3% Ca-cl
- Order 120ST 59 1/2 Permud 4% Gel. 3% Ca-cl - 8 5/8" Plug
- spot with Drill Stem with Heavy Mud Between all plugs
- 1ST Plug @ 960^{FE} w/ 60ST cnt.
- 2ND Plug @ 270^{FE} w/ 40ST cnt.
- 3RD Plug - solid bridge @ 40^{FE} w/ 10ST cnt.
- 10ST In Rat Hole

Very truly yours, By Sun Hunt
STATE CORPORATION COMMISSION

Marion Schreder AUG 13 1981
Conservation Division Agent CONSERVATION DIVISION
Wichita, Kansas