



15-051-03691-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. B.A. Hartnett of Champlin Petroleum Co.

RECEIVED
STATE CORPORATION COMMISSION
FEB - 2 - 1982

date requested permission to plug the following described well:

Operator's Full Name: Champlin Petroleum Co.

CONSERVATION DIVISION
Wichita, Kansas

Complete Address: P.O. Box 9367 Fort Worth, Texas 76107

Lease Name: Slimmer Well No. 6

Location: NE SE NW Sec. 2 Twp. 11 Rge. 17 (E) (W)

County: Ellis Total Depth: 3892'

Abandoned Oil Well Gas Well Input Well SWD Well XXX D&A

Other well as hereafter indicated: Start of a sink hole.

Mr. Hartnett was instructed to plug the well as follows:

10 3/4"-160' S.P. cuc. W/ 100 sacks common. 6 5/8" set at 3835' W/ 1333
sacks common cuc. 4 7/8" Bit, 2-3 1/2" Drill collars and 590' of 2 7/8"
tubing stuck in hole at 650'. Pumped into 2 7/8" tubing with pump truck.

Jan. 25-82 pumped in 500 sacks common cement.
Jan. 26-82 pumped in 300 sacks 50/50 posmix 6% Gel.-3% Cal.Cl. and pumped
between tubing and 6 5/8" casing 60 sacks Gel. and 300 sacks 50/50 posmix
3% Gel.-3% Cal.Cl..
Jan. 27-82 pumped in 500 sacks Halliburton Light with 5 pounds Gilsonite
and 1/4 pound Flo-cele per sack.

Very truly yours,

Jan. 28-82 Filled to top with 25 sacks Halliburton Light with 1/4 pound Flo-Cele

[Signature]
Conservation Division Agent