

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum, Inc.

Complete Address 300 W. Douglas Wichita, Kansas 67202

Lease Name Edie Well No. 1

Location NE SE SE Sec. 30 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3550'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Garvey Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 5:45 A Day 10 Month 10 Year 1971

The above well was plugged as follows:

RTD 3550' 8 5/8 csg set at 303' cwc 210 sk Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk  
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 25 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. M... ..  
Well Plugging Supervisor

DATE 10-13-71

INV. NO. 4459-W