

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name DeHoff "A" Well No. 5

Location C NW SE NW Sec. 30 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3378'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11 A Day 25 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 3378' 8 5/8 csg set at 1005' cwc 300 sk. El. 1826' GL.

5 1/2 csg set at 3341' cw 150 sk cmt.

Set 5 1/2 wood plug at 3250' -poured 10' sd -dumped 5 sk cmt W/dump bailer. (3200-3250)

Cutoff and recovered 1330' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released plug and

pumped 90 sk Halib.-Light cmt. 400 lbs Shutin Pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 2/28/72

INV. NO. 5234-U