



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address: Box 553 Russell, Kansas 67665

Lease Name DeHoff Well No. 1

Location NW NW NW Sec. 30 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3368'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12:30P Day 7 Month 11 Year 1969

The Above well was plugged as follows:

Total Depth 3368' 8 5/8 csg set at 1038' cwc 300 sk.

5 1/2 csg set at 3334' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3300-3368) Dumped 5 sk cmt W/dump bailer/ (3260-3300)

Cutoff and recovered 2450' of 5 1/2 csg.

~~REDACTED SECTION~~

Pumped thru 8 5/8 swage with plug and 150 sk 50-50 poz cmt 2% gel. (0-525)

SI pres. 700 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/10/69
INV. NO. 803-W