

15-167-00002-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW SW NE

SEC. 12 TWP. 13 RGE. 13

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Dauber

Operator Flynn Oil Co Address 809 Thompson Bldg Tulsa,

Field \_\_\_\_\_ County Russell

Total Depth 2855 Feet.

(Describe briefly the manner in which the well was plugged)

9 5/8" at 315', circulated with cement - ~~sax~~ at 7" at  
2813' with 40 & 50 & 125 sax cement behind.

Filled with chat to 2800', set 5 sax cement with dump  
bailer, pulled 1170' 7", pumped hole full mud with 20 sax  
Aquagel, pumped Halliburton plug to 225' followed by  
85 sax cement, filling hole from 225' to 0' with cement.  
Mudding and Cementing by Halliburton Co.

**PLUGGING**  
FILE SEC 12 T 13 R 13  
BOOK PAGE 31 LINE 29

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 22 1952  
07-22-1952  
CONSERVATION DIVISION  
Wichita, Kansas

*Edon Perry*  
District Conservation Agent

Date \_\_\_\_\_  
7-13-52