

15-167-00352-00-00

[Handwritten mark]

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 12 TWP. 13 RGE. 13

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Dauber

Operator B & R Drg. Co. TUC Address Russell, Kans

Field _____ County Russell

Total Depth 3002 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 293' circulated with cement- 5 1/2" at 2997'

Plugged back, Lane wells plugs and cement to 2820' - perforations

at 2801' - Chat from 2820' to 2795' and 5 sax cement - Pulled

2657' of 5 1/2" and heavy mud to 293', wood plug, rock and 15 sax

cement - Heavy mud to 35', wood plug, rock and 10 sax cement.

09-06-1949
SEP 6 X 1949

STATE CORPORATION
COMMISSION
KANSAS

[Signature]
District Conservation Agent

Date 9-3-49

PLUGGING
FILE SEC 12 TWP 13 RGE 13
BOOK PAGE 112 LINE 44