

15-007-16669-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Tedrow Well No. # 1

Location C NW SW Sec. 20 Twp. 32 Rge. 13 (E) (W) W

County Barber Total Depth 4604'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 3:45 PM Day 2nd Month September Year 1965

The Above well was plugged as follows:

291' of 8 5/8" surface cement circulated. 4603' of 5 1/2" long string.

cemented with 150 sacks. Plug back to 4567'. Top perferation 4545'.

Bottom plug was pushed to 4000', and 30' of sand bridge, and cemented

with 5 sacks. 3673' of 5 1/2" long string was recovered from the hole.

Hole was bailed down to 275', rock bridge from 275 to 265', and cemented

with 4 yards of ready-mix cement to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: Archie Elving
Well Plugging Supervisor

SEP 3 1965

INVOICED

DATE 9/3/65

INV. NO. 1746-W

CONSERVATION DIVISION
Wichita, Kansas