

15-051-20319-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-2-1968
OCT 2 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kaiser - Francis

Complete Address: 909 Palace Bldg., Tulsa, Oklahoma

Lease Name Chrisler "F" Well No. 1

Location NW SW NW Sec. 34 Twp. 11 Rge. 16 (E) (W) XX

County Ellis Total Depth 3005

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drlg.

Address: Wichita, Ks. License No.

Operation Completed: Hour 9:30A Day 30 Month 9 Year 1968

The Above well was plugged as follows:

RTD 3005' 8 5/8 csg set at 257' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cmt.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cmt to base
of cellar. Plugged rat hole with 2 sc cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo P. Massey
Well Plugging Supervisor

INVOICED

DATE 10/2/68
INV. NO. 8567-W