

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,784 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill St., Plainville, Ks. 67663

Lease Name Nadel-Gussman Well No.#1

Location SW NE NW Sec.34 Twp. 11 Rge. 16 (East) (West) (West)

County Ellis Total Depth 3410'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drilling Company, Inc.

Address 308 W. Mill St., Plainville, Ks. 67663 License No. _____

Operation Completed: Hour: 10:00PM Day: 27th Month: Jan. Year: 19 82

Plugging Operations attended by Agent?: All XXX Part _____ None _____

The above well was plugged as follows:

8 5/8"-955' s.p. cuc. w/375 sacks 60/40 posmix-3% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 310' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

Amount of Surface Casing: 955' of 8 5/8".

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED
2-3-82
9182W

RECEIVED
STATE CORPORATION COMMISSION
2-2-1982
FEB - 2 1982

Signed: _____
Conservation Division Agent
Wichita, Kansas