

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

8/19/10

Operator: License # 5316
Name: FALCON EXPLORATION, INC.
Address: 125 N. MARKET, SUITE 1252
City/State/Zip: WICHITA, KS 67202
Purchaser: NA
Operator Contact Person: MIKE MITCHELL
Phone: (316) 262-1378
Contractor: Name: VAL ENERGY INC.
License: 5822
Wellsite Geologist: JIM HALL

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____

Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____

Deepening Re-perf. Conv. to Enhr./SWD

Plug Back Plug Back Total Depth

Commingled Docket No. _____

Dual Completion Docket No. _____

Other (SWD or Enhr.?) Docket No. _____

5/18/08 6/01/08
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 025-21456-0000

County: CLARK

NE NE NW SW Sec. 4 Twp. 32 S. R. 21 East West

2600 feet from (S) / N (circle one) Line of Section

1000 feet from E / (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW SW

Lease Name: WILLIS Well #: 1-4

Field Name: WC

Producing Formation: _____

Elevation: Ground: 1966 Kelly Bushing: 1976

Total Depth: 5381 Plug Back Total Depth: _____

Amount of Surface Pipe Set and Cemented at 689 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from _____

feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan PANH-20-08
(Data must be collected from the Reserve Pit)

Chloride content 8500 ppm Fluid volume 1130 bbls

Dewatering method used FREE FLUIDS HAULED TO SWDW

Location of fluid disposal if hauled offsite: _____

Operator Name: GENE R DILL & ROBERTS RESOURCES

Lease Name: REGIER SWD & MARY #1 SWD License No. 6652;32781

Quarter _____ Sec. 16 Twp. 29S S. R. 18 East West

County: MEADE; KIOWA Docket No.: C21232;D28396

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: _____

Title: PRESIDENT Date: 8/19/08

Subscribed and sworn to before me this 18TH day of AUGUST

20 08

Notary Public: Rosann M Schippers

Date Commission Expires: 9/28/11

KCC Office Use ONLY

Letter of Confidentiality Received

If Denied, Yes Date: _____

Wireline Log Received

Geologist Report Received

UIC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 19 2008

ROSANN M. SCHIPPERS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 9/28/11

CONSERVATION DIVISION
WICHITA, KS

Operator Name: **FALCON EXPLORATION, INC.** Lease Name: **WILLIS** Well #: **1-4**
 Sec. **4** Twp. **32** S. R. **21** East West County: **CLARK**

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <i>(Attach Additional Sheets)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Samples Sent to Geological Survey	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	TORONTO	4208	-2232
Electric Log Run <i>(Submit Copy)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	LANSING	4406	-2430
List All E. Logs Run:		BKC	4864	-2888
CNL/CDL;DIL;BHCS;MEL		MARMATON	4880	-2904
		MORROW SH	5132	-3156
		MORROW SS	5154	-3178
		MISSISSIPPIAN	5246	-3270

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
CONDUCTOR	32"	20"		40	GROUT		
CONDUCTOR	17-5/8	13-3/8"	48#	384.75376	65/35/6, CLASS 'A'	675	2% GEL, 3% CC
SURFACE	12-1/4"	8-5/8"	23#	689	65/35/6;CLASS 'A'	300	2% GEL, 3% CC

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

*per CP 23
abr. in
sup.
KLU
1/11/08*

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth

TUBING RECORD		Size	Set At	Packer At	Liner Run	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.			Producing Method			
			<input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity	

Disposition of Gas METHOD OF COMPLETION Production Interval

Vented Sold Used on Lease
 Open Hole Perf. Dually Comp. Commingled
(If vented, Submit ACO-18.)
 Other (Specify) _____

ALLIED CEMENTING CO., LLC. 34033

SHIP TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Medicine Lodge, KS

DATE <u>18 MAY 08</u>	SEC. <u>04</u>	TWP. <u>32s</u>	RANGE <u>21w</u>	CALLED OUT <u>7:30 AM</u>	ON LOCATION <u>8:30 AM</u>	JOB START <u>6:30 AM</u>	JOB FINISH <u>3:30 PM</u>
BASE <u>Willis</u>	WELL# <u>1-4</u>	LOCATION <u>Sitka, Tut, N to mm. 20, E into</u>			COUNTY <u>Clark</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)							

CONTRACTOR Val #2 OWNER Falcon Expto.

TYPE OF JOB Conductor

PIPE SIZE 7 1/2 T.D. 381

HOUSING SIZE 13 3/8 DEPTH 376

PIPE SIZE DEPTH

PIPE DEPTH

PIPE DEPTH

DEPT. MAX 500 MINIMUM —

DEPT. LINE SHOE JOINT 37

CEMENT LEFT IN CSG. 37

TESTS.

CEMENT PLACEMENT 55 Bbls Fresh H₂O

EQUIPMENT

JMP TRUCK 352 CEMENTER D. Fazio / T. Demareo
HELPER M. Becken

JLK TRUCK 368 DRIVER R. Romans

JLK TRUCK DRIVER

CEMENT

AMOUNT ORDERED 250sx65:35:6+3%cc + 1/4 # Flogel AND 250sx "A" + 3%cc + 2% gel

COMMON	<u>250 A</u>	@ <u>14.20</u>	<u>3550.00</u>
POZMIX		@	
GEL	<u>5</u>	@ <u>18.75</u>	<u>93.75</u>
CHLORIDE	<u>17</u>	@ <u>52.45</u>	<u>891.65</u>
ASC		@	
	<u>ALW 250</u>	@ <u>13.35</u>	<u>3337.50</u>
	<u>F10 Seal 63 #</u>	@ <u>2.25</u>	<u>141.75</u>
		@	
		@	
		@	
		@	
HANDLING	<u>538</u>	@ <u>2.15</u>	<u>1156.70</u>
MILEAGE	<u>65 X 538 X .09</u>		<u>3147.30</u>
TOTAL			<u>12318.65</u>

REMARKS:

pipe on Btm, Break Core, Pump 100sx life weight, dump 100sx tail cement, Stop, Release Plug, set Disp. w/ Fresh H₂O, Washup on Plug, Slow Rate. Did not Bump Plug at 55 Bbls total Disp., Shot, Did not Circ. Cement, Rig up 150' of 1", Pump 50sx life, 100sx tail cement, Did NOT top off, set 1 1/2 hrs, Rig up 60' of 1", Pump 50sx life weight, 50sx tail cement, Did NOT top off, cement at APPROX 45' from surface

SERVICE

DEPTH OF JOB	<u>376</u>		
PUMP TRUCK CHARGE	<u>0-300'</u>		<u>917.00</u>
EXTRA FOOTAGE	<u>76'</u>	@ <u>.80</u>	<u>60.80</u>
MILEAGE	<u>65</u>	@ <u>7.00</u>	<u>455.00</u>
MANIFOLD	<u>Head rental</u>	@ <u>113.00</u>	<u>113.00</u>
		@	
		@	

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 19 2008

TOTAL 1545.80

CONSERVATION DIVISION
MICHIGAN & FLOAT EQUIPMENT

1-TWP	@ <u>79.00</u>	<u>79.00</u>
1-Basket	@ <u>310.00</u>	<u>310.00</u>
1-Baffle Plate	@ <u>186.00</u>	<u>186.00</u>
	@	
	@	

TOTAL 575.00

SALES TAX (If Any) _____

TOTAL CHARGES ~~1545.80~~

DISCOUNT ~~1545.80~~ IF PAID IN 30 DAYS

CHARGE TO: Falcon Expto.

ADDRESS: Box 551

CITY: Russell STATE: KS ZIP: 67665

Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Leon Kikwa

SIGNATURE Leon Kikwa

ANY APPLICABLE TAX
WILL BE CHARGED
UPON INVOICING

13 3/8"

ALLIED CEMENTING CO., LLC. 31081

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Medicine Lodge, KS.
5-19 5-20 5-20 5:20 AM

DATE <u>5-20-09</u>	SEC. <u>4</u>	TWP. <u>32S</u>	RANGE <u>21W</u>	CALLED OUT <u>10:00 P.M</u>	ON LOCATION <u>12:00 AM</u>	JOB START <u>10:00 AM</u>	JOB FINISH <u>7:30 AM</u>
LEASE <u>Willis</u>	WELL # <u>1-4</u>	LOCATION <u>SITKA Jct., N TO MM #20</u>			COUNTY <u>Clark</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>			E/INTO				

CONTRACTOR Val Rig #2
 TYPE OF JOB TOP OUT 13 3/8
 HOLE SIZE 17 1/2 T.D.
 CASING SIZE 13 3/8 DEPTH
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG. See Remarks
 PERFS. See Remarks
 DISPLACEMENT See Remarks

KCC EQUIPMENT

PUMP TRUCK CEMENTER Thomas Dannerow
 # 352 HELPER Mike B.
 BULK TRUCK
 # 389 DRIVER Colt H.
 BULK TRUCK
 # 363 DRIVER Randy F.

OWNER Falcon Exploration

CEMENT
 AMOUNT ORDERED (200sf 65' 35' 6" + 3% CC + 1/4" Handling charged Ticket #310)
Floral), 300sf class A + 3% CC + 2% GEL,
100sf class A + 6% Gyp + 1% GEL + 3% CC + 1% Am. Chlor.
(used 100sf A/3/2 + 75sf A + 6% Gyp + 1% GEL + 1% Am. Chlor. + 1% Am. Chlor.)
 COMMON 175 A @ 14.20 2485.00
 POZMIX @
 GEL 3 @ 18.75 56.25
 CHLORIDE 6 @ 52.45 314.70
 ASC @
Gyp Seal 4 @ 26.30 105.20
Ammonium chloride 2 @ 45.35 90.70
 @
 @
 @
 @
 @
 @
 HANDLING 400 @ 2.15 860.00
 MILEAGE 65 X 400 X .09 2340.00
 TOTAL 6251.85

REMARKS:

TOP out hole w/30 sf A/3/2, cement @ surface,
cement fell, top out w/30sf A/3/2, cement
fell, top out w/40sf A/3/2, cement fell,
top out w/50 sf A + 6% Gyp + 1% GEL + 3% CC +
1% Am. chlor., cement fell, top out w/25sf
A + 6% Gyp + 1% GEL + 3% CC + 1% Am. chlor., cement
stayed @ surface

Thank you

CHARGE TO: Falcon Exploration
 STREET Box 551
 CITY Russell STATE KS ZIP 67665

SERVICE

DEPTH OF JOB 917.00
 PUMP TRUCK CHARGE
 EXTRA FOOTAGE @
 MILEAGE 65 @ 7.00 455.00
 MANIFOLD @
ADDITIONAL hrs. 4 @ 225.00 900.00
 RECEIVED @

KANSAS CORPORATION COMMISSION

AUG 19 2008

TOTAL 2272.00

CONSERVATION DIVISION
WICHITA, KANSAS PLUG & FLOAT EQUIPMENT

NAME @
 @
 @
 @
 @

TOTAL

SALES TAX (If Any)
 TOTAL CHARGES
 DISCOUNT IF PAID IN 30 DAYS

ANY APPLICABLE TAX
WILL BE CHARGED
UPON INVOICING

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Leon Kuhro
 SIGNATURE Leon Kuhro

ALLIED CEMENTING CO., LLC. 31082

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Medicine Lake, KS
5-19 5-20 5-21 5-21

DATE <u>5-20-08</u>	SEC. <u>4</u>	TWP. <u>32S</u>	RANGE <u>21W</u>	CALLED OUT <u>10:00 PM</u>	ON LOCATION <u>12:00 AM</u>	JOB START <u>5:30 AM</u>	JOB FINISH <u>6:00 AM</u>
LEASE <u>Willis</u>	WELL # <u>1-4</u>	LOCATION <u>Sitka Jet, N To MM #20, E</u>			COUNTY <u>CLARK</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>			INTO				

CONTRACTOR VAL Rig #2

TYPE OF JOB Surface

HOLE SIZE 12 1/4" T.D. 695'

CASING SIZE 8 5/8" 24" DEPTH 695'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 1,000 MINIMUM 100

MEAS. LINE _____ SHOE JOINT 42.63'

CEMENT LEFT IN CSG. 42.63'

PERFS. _____

DISPLACEMENT 42 1/2 BBL Fresh water

EQUIPMENT KCC

PUMP TRUCK CEMENTER Thomas Dammrow

352 HELPER Mike B.

BULK TRUCK _____

303 DRIVER Randy F.

BULK TRUCK _____

_____ DRIVER _____

OWNER Falcon Exploration

CEMENT
AMOUNT ORDERED 2005x 65.35' @ 38 cc + 1/4" flo seal/sk, 1005x class A + 32 cc + 2% GEL

COMMON	<u>100 A</u>	@	<u>14.20</u>	<u>1420.00</u>
POZMIX		@		
GEL	<u>2</u>	@	<u>18.75</u>	<u>37.50</u>
CHLORIDE	<u>10</u>	@	<u>52.45</u>	<u>524.50</u>
ASC		@		
	<u>200 ALW</u>	@	<u>13.35</u>	<u>2670.00</u>
	<u>Flo Seal 50 *</u>	@	<u>2.25</u>	<u>112.50</u>
		@		
		@		
		@		
		@		
HANDLING	<u>324</u>	@	<u>2.15</u>	<u>696.60</u>
MILEAGE	<u>65 x 324 x .09</u>			<u>1895.40</u>
				TOTAL <u>7356.50</u>

REMARKS:

Pipe on Bottom, Break circulation, Pump 5 BBL Fresh Ahead, Pump cement - 2005x 65.35' @ 38 cc + 1/4" flo seal/sk, 1005x class A + 32 cc + 2% GEL, stop pumps, Release Plug, Start D, replace cement, slow rate, Pump Plug, Floathold, Displace w/ 42 1/2 BBL Fresh water, cement circulated to surface
THANK YOU

SERVICE

DEPTH OF JOB	<u>695'</u>		
PUMP TRUCK CHARGE	<u>0-300'</u>		<u>917.00</u>
EXTRA FOOTAGE	<u>395'</u>	@	<u>.80</u> <u>316.00</u>
MILEAGE	<u>65</u>	@	<u>7.00</u> <u>N/C</u>
MANIFOLD		@	
<u>Head Rental</u>	<u>1</u>	@	<u>113.00</u> <u>113.00</u>
<u>Additional Hrs</u>	<u>4</u>	@	<u>225.00</u> <u>900.00</u>

CHARGE TO: Falcon Exploration

STREET Box 551

CITY Russell STATE Ks ZIP 67665

RECEIVED
KANSAS CORPORATION COMMISSION TOTAL 2246.00

AUG 19 2008

PLUG & FLOAT EQUIPMENT
CONSERVATION DIVISION
WICHITA, KS

TOP Rubber Plug	<u>1</u>	@	<u>113.00</u>	<u>113.00</u>
AFU Insert	<u>1</u>	@	<u>377.00</u>	<u>377.00</u>
Centralizers	<u>2</u>	@	<u>62.00</u>	<u>124.00</u>
Basket	<u>1</u>	@	<u>248.00</u>	<u>248.00</u>
		@		

TOTAL 862.00

SALES TAX (If Any) _____

TOTAL CHARGES ~~862.00~~

DISCOUNT ~~862.00~~ IF PAID IN 30 DAYS

PRINTED NAME Leon Kuhn

SIGNATURE Leon Kuhn

ANY APPLICABLE TAX
WILL BE CHARGED
UPON INVOICING

ALLIED CEMENTING CO., LLC.

30385

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: LIBERAL, KS

DATE <u>6-1-08</u>	SEC. <u>4</u>	TWP. <u>32</u>	RANGE <u>21</u>	CALLED OUT	ON LOCATION	JOB START	JOB FINISH
LEASE <u>WILLIS</u>	WELL # <u>1-4</u>	LOCATION <u>ST. Ka N 1/4 mi #20</u>			COUNTY <u>CLARK</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)		<u>Into</u>					

CONTRACTOR VAC #2

TYPE OF JOB PLUG TO Abandon

HOLE SIZE 7 1/8 T.D.

CASING SIZE 6 5/8 DEPTH 600'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT

CONFIDENTIAL
AUG 19 2008
EQUIPMENT
KCC

PUMP TRUCK CEMENTER BOB

417 HELPER Don

BULK TRUCK

45 DRIVER MARRY

BULK TRUCK

DRIVER

REMARKS:

Mix 50SK Plug at 710'
Mix 50SK Plug at 390'
Mix 20SK Plug at 60'
Mix 15SK
Mix 10SK Mouse Hole

Thank You

CHARGE TO: FALCON Exp

STREET

CITY STATE ZIP

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME

SIGNATURE John

OWNER SAME

CEMENT

AMOUNT ORDERED 145 60/40 40% GEL

COMMON	<u>87</u>	@	<u>1420</u>	<u>1235.46</u>
POZMIX	<u>58</u>	@	<u>720</u>	<u>417.60</u>
GEL	<u>53K</u>	@	<u>1875</u>	<u>93.75</u>
CHLORIDE		@		
ASC		@		
	<u>145 60/40/4</u>	@	<u>12.65</u>	<u>1834.25</u>
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>149</u>	@	<u>2.15</u>	<u>320.35</u>
MILEAGE	<u>1095Kmi</u>			<u>1005.75</u>
TOTAL				<u>4907.10</u>

SERVICE

DEPTH OF JOB 710

PUMP TRUCK CHARGE 917.00

EXTRA FOOTAGE @

MILEAGE 75 @ 7.00 525.00

MANIFOLD @

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 19 2008
CONSERVATION DIVISION
WICHITA, KS

TOTAL 1442.00

@

@

@

@

@

TOTAL

SALES TAX (If Any)

TOTAL CHARGES

DISCOUNT IF PAID IN 30 DAYS