

CONFIDENTIAL

ORIGINAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

8/29/10

Operator: License # 33074
Name: Dart Cherokee Basin Operating Co., LLC
Address: P O Box 177
City/State/Zip: Mason MI 48854-0177
Purchaser: Oneok
Operator Contact Person: Beth Oswald
Phone: (517) 244-8716
Contractor: Name: McPherson
License: 5675
Wellsite Geologist: Bill Barks

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: AUG 29 2008

Well Name: KCC
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

5-9-08 5-13-08 6-2-08
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 125-31600-00-00
County: Montgomery
SE NE SE Sec. 12 Twp. 33 S. R. 13 East West
1830' FSL feet from S / N (circle one) Line of Section
550' FEL feet from E / W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: A&C Vannoster Well #: C4-12
Field Name: Cherokee Basin Coal Gas Area
Producing Formation: Penn Coals
Elevation: Ground: 854' Kelly Bushing: _____
Total Depth: 1615' Plug Back Total Depth: 1608'
Amount of Surface Pipe Set and Cemented at 43 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan ALT II NH 10-9-08
(Data must be collected from the Reserve Pit)
Chloride content NA ppm Fluid volume 110 bbls
Dewatering method used Empty w/ vac trk and air dry
Location of fluid disposal if hauled offsite:
Operator Name: Dart Cherokee Basin Operating Co., LLC
Lease Name: Reitz B4-35 SWD License No.: 33074
Quarter NE Sec. 35 Twp. 34 S. R. 14 East West
County: Montgomery Docket No.: D-28391

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: Engr Clerk Date: 8-29-08
Subscribed and sworn to before me this 29 day of August
20 08
Notary Public: Brandy R. Allcock
Date Commission Expires: 3-5-2011

BRANDY R. ALLCOCK
Notary Public Michigan
Jackson County
Commission Expires
March 05, 2011

acting in engham

KCC Office Use ONLY
 Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
RECEIVED
KANSAS CORPORATION COMMISSION
SEP 02 2008

CONSERVATION DIVISION
WICHITA, KS

Operator Name: Dart Cherokee Basin Operating Co., LLC Lease Name: A&C Vannoster Well #: C4-12
 Sec. 12 Twp. 33 S. R. 13 ✓ East West County: Montgomery

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No (Attach Additional Sheets) Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Submit Copy) List All E. Logs Run: High Resolution Compensated Density Neutron & Dual Induction	Log Formation (Top), Depth and Datum <input checked="" type="checkbox"/> Sample Name Top Datum See Attached
--	---

CONFIDENTIAL
 AUG 29 2008

CASING RECORD							
New				Used			
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surf	11"	8 5/8"	24#	43'	Class A	8	
Prod	6 3/4"	4 1/2"	9.5#	1609'	Thick Set	165	See Attached

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
6	1434.5' - 1438'	1025# sd, 90 BBL fl	
6	1077' - 1079'	150 gal 15% HCl, 3070# sd, 115 BBL fl	

TUBING RECORD		Size 2 3/8"	Set At 1564'	Packer At NA	Liner Run Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
Date of First, Resumed Production, SWD or Enhr. 6-6-08		Producing Method Flowing <input type="checkbox"/> Pumping <input checked="" type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain) <input type="checkbox"/>			
Estimated Production Per 24 Hours	Oil Bbls. NA	Gas Mcf 1	Water Bbls. 25	Gas-Oil Ratio NA	Gravity NA

Disposition of Gas: Vented Sold Used on Lease (If vented, Sumit ACO-18.)

METHOD OF COMPLETION: Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval: _____

RECEIVED
 KANSAS CORPORATION COMMISSION

SEP 02 2008

CONSOLIDATED OIL WELL SERVICES, LLC
 P.O. BOX 884, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8676

ENTERED

TICKET NUMBER 14036
 LOCATION Evreks
 FOREMAN Troy Strickler

**TREATMENT REPORT & FIELD TICKET
 CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-14-08	2368	Vannoster A+C C4-12				MO
CUSTOMER Dart Cherokee Basin			TRUCK #			
MAILING ADDRESS 211 w. Myrtle			DRIVER		TRUCK #	
CITY Independence			DRIVER		TRUCK #	
STATE KS			DRIVER		TRUCK #	
ZIP CODE 67301			DRIVER		TRUCK #	

JOB TYPE Logstring HOLE SIZE 6 7/8" HOLE DEPTH 1615' CASING SIZE & WEIGHT 4 1/2" 9.5"
 CASING DEPTH 1609' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 13.2# SLURRY VOL 50.8 Bbl WATER gal/sk 8.0 CEMENT LEFT in CASING 0
 DISPLACEMENT 26 Bbl DISPLACEMENT PSI 900 MIX PSI 1400 RATE _____

REMARKS: Safety Meetng: Rig up to 4 1/2" casing. Break Circulation w/ 30 Bbl water
Pump back Gel-Flush w/ Hulls 5 Bbl water, 10 Bbl soap water, 20 Bbl water,
16 Bbl Dye water. Mixed 165 SK Thick Set Cement w/ 8" Kol-Seal @ 13.2#
Wash out Pump + lines. Release Plug. Displace w/ 26 Bbl water. Final Pump
Pressure 900 PSI. Pump Pk to 1400 PSI. wait 5 min. Release Pressure.
Flot Hold Good Cement to surface = 7 Bbl Slury to Pk.
Job Complete

AUG 29 2008
 MOG

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401	1	PUMP CHARGE	875.00	875.00
5406	40	MILEAGE 2nd of 2 wells	3.45	138.00
1126A	165 SK	Thick Set Cement	16.20	2673.00
1110A	1320#	Kol-Seal 8"/SK	.40#	528.00
1118A	300#	Gel-Flush	.16#	48.00
1105	50#	Hulls	.37#	18.50
5407		Ton-Mileage	m/c	300.00
4404	1	4 1/2" Top Rubber Pk	42.00	42.00
1143	1 gal	Soap	36.85	36.85
1140	2 gal	Bi-side	27.70	55.40
RECEIVED KANSAS CORPORATION COMMISSION SEP 02 2008 CONSERVATION DIVISION WICHITA, KS				
Thank You!			Sub total	4576.75
			5.3% SALES TAX	175.40
			ESTIMATED TOTAL	4752.15

AUTHORIZATION [Signature] TITLE _____ DATE _____