

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20849-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 21-21S-11W
4399 feet from S Section Line, 1930 feet from E Section Line
Lease Name: SMITH ESTATE B Well #: 3-21
County: STAFFORD Total Vertical Depth: 3435 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		725		WITH 2 SX CMT
CIBP		3350		WITH 4 SX CMT
SURF	8.625	311		
PROD	4.5	3435	0	WITH 135 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 06/05/2008 12:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

CIBP @ 3350' & 4 SX CMT. 1ST PLUG SET CIBP @ 725' & 2 SX CMT. TEST CASING TO 400#. 2ND PLUG PERFORATE AT 690'. PUMP 90 SX CMT DOWN 4 1/2" CASING. MAXIMUM PRESSURE 1200#. 3RD PLUG PUMP 110 SX CMT DOWN 8 5/8" CASING. MAXIMUM PRESSURE 500#.

Perfs:

Top	Bot	Thru	Comments
3542	3550		

INVOICE
DATE 7/01/08
INV. NO. 2009060001

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed Steve Durrant
(TECHNICIAN)

RECEIVED
AUG 13 2010
KCC DODGE CITY