

4- 041363

15-051-22567-00-00

121R

4-14

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-051-22,567

4290  
8/26/10

SE NE NE /4 SEC. 04 , 11 S , 17 W  
-4920- feet from S section line  
330 feet from E section line

Operator license# 5296

Lease Orlan Carmichael well # 3

Operator: Helmrich & Payne

County Ellis

Address: Box 558  
Garden City, Kansas 67846

Well total depth <sup>3519'</sup> ~~356~~ feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 263 feet  
w/135 sx.

Aband. oil well     , Gas well     , Input well X, SWD     , D & A     

Plugging contractor: Halliburton Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:30A.M. Day: 14 Month: April Year: 92

Plugging proposal received from: Leland Felhoelter

Company: Plainville, Kansas 67663 Phone:     

Were: 5 1/2" casing set @ 3525' w/150 sx. Perf. @ 3432' - 3495'.  
Anhy. - Perf. @ 1160'. Dakota @ 600'.  
Ordered 300 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 600# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 1:00P.M., Day: 14, Month: April, Year: 92

Actual plugging report: R.I.H. with tubing to 3420''. Spot 75 sxs. cement with 200# hulls. Pull tubing @ 2000'. Spot 95 sxs. cement with 200# hulls. P.O.O.H. with tubing. Hooked-up to 5 1/2" casing. Squeezed 75 sxs. cement with 100# hulls. Max. P.S.I. 400#. Sut in P.S.I. 200#. Hook-up to 8 5/8" S.P. Squeezed 55 sxs. cement with 100# hulls, Mixed in cement. Max. P.S.I. 700#. Shut in P.S.I. 600#.

Remarks:  
Condition of casing(in hole):GOOD X BAD      Anhy.plug:YES X NO       
Bottom plug(in place):YES X ,CALC      ,NO      Dakota plug:YES X ,NO       
Plugged through TUBING X , CASING     . Elevation: 1920 GL     

I did [ X ] did not [      ] observe the plugging.

Dennis L. Hamel  
MAP 1625'

INVOICED  
DATE 4-28-92  
WIK NO 35074

(agent)  
Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
15-051-22567-00-00  
APR 24 1992

170