

15-051-20757-00-00
KANSAS

Form CP-3
Rev. 6-4-68

df
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers, Inc.
Complete Address Russell, Kansas
Lease Name Amece - Carmichael Well No. 1
Location NW NE SE Sec. 5 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3170'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 4:30 A Day 6 Month 9 Year 1971

The above well was plugged as follows:

RTD 3170' 8 5/8 csg set at 265' cwc Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-10-71
INV. NO. 4307-W

Signed: Leo J. Masny
Well Plugging Supervisor