

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

5-20-1966  
MAY 20 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name D E D Drilling Company Inc

Complete Address: 307 Schweiter Bldg. Wichita, Kansas

Lease Name Cumple Well No. 1

Location N/2 S/2 NW Sec. 5 Twp. 11 Rge. 17 (E) (W) X

County Ellis Total Depth 3150

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: C. O. Tools by Halib.

Address:      License No.     

Operation Completed: Hour 5A Day 19 Month 5 Year 1966

The Above well was plugged as follows:

Total Depth 3150 ft. 8 5/8 set at 230' CW 190 sacs Cem.

Cement pits circulated hole with heavy mud, set cementing plug at 600 ft.

and displaced 25 sac cement thru drill pipe, heavy mud to 230 ft., set

cementing plug and displaced 20 sac cement thru drill pipe, heavy mud to 40 ft.,

set cementing plug, 1/2 sac hulls and 8 sac cement, cementing to base of collar.

Plugged Rat Hole with 2 sacs Cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Lio Massey  
Well Plugging Supervisor

DATE 5/20/66  
INV. NO. 3245-W