

15-051-03291-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 40-26

LOCATION SE SW SW

SEC. 6 TWP. 11 RGE. 17W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. B-3 Lease Henderson

Operator Stanolind Oil & Gas Co. Address Box 389 Hays, Kans

Field _____ County Ellis

Total Depth 3523 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe briefly the manner in which the well was plugged)

10 3/4" at 1240' circulated with cement - 7" at 3512' with
175 sax cement behind.

Leak in casing at 2750, filled with sand to 2740, set 5 sax
cement at 2740', pulled 2400' 7" - filled with mud to 300',
set rock and 25 sax cement, heavy mud to 30', set rock and
10 sax cement to bottom cellar.

STATE OF KANSAS
DIVISION OF CONSERVATION

3-16-1956

District Conservation Agent

3-12-56

Date _____

PLUGGING

FILE SEC 6 TWP 11 R 17W
BOOK PAGE 40 LINE 26

CONSERVATION DIVISION
WICHITA, KANSAS