

15-051-05664-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-25-1968
MAR 25 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pan American Petroleum Corporation

Complete Address: P. O. Box 432 Liberal, Kansas 67901

Lease Name N. Henderson "B" Well No. 1

Location SE SE SW Sec. 6 Twp. 11 Rge. 17 (E) (W) X

County Ellis Total Depth 3532

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4 P Day 21 Month 3 Year 1968

The Above well was plugged as follows:

Total Depth 3532 16" at 74' cwc 10 3/4" at 1164' cwc.

5 1/2 csg set at 3472' cw 200 sc cement.

5 1/2 PBTB 3350' Top perf. 3034'

Filled with sand to 300' and dumped 5 sc cement with dump bailer.

Recov. 2060' of 5 1/2 csg.

Set plug and rock bridge (425-400)

Filled to surface with 8 yds readymix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/26/68

INV. NO. 17469-W

Signed: L. F. Massey
Well Plugging Supervisor