

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
9-24-1963  
SEP 24 1963  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Pan American Pet Corp

Complete Address: Box 1654 Oklahoma City, Okla

Lease Name Katherine Gumble Well No. 2

Location N $\frac{1}{2}$  SW SE Sec. 6 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3447

Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Barnes & Sons

Address: Russell, Kans License No. 9

Operation Completed: Hour 1PM Day 16 Month 9 Year 63

The Above well was plugged as follows:

10 3/4" 1152' circulated with cement - 7' 3446' - Perf 3420' - PB with rockto 3420', set 2 sax calseal and 3 sax cement.

Pulled 2540' 7" to 550' - circulated hole with heavy gel mud through 7" - 27 sax gel - displaced 20 sax cement through 7" at 500', heavy mud to 200' - displaced 20 sax cement through 7" at 200', - heavy mud to 30' set bridge and filled to bottom cellar with cement.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/24/63  
INV. NO. 4490-u

Signed: Edon Peety  
Well Plugging Supervisor